

### James Rickert, President, Division 5

Audie Butcher, Director, Division 2

### Ivar Amen, Vice President, Division 4

**Garrett Wallis**,

Director, Division 3

### Ronnean Lund, Director, Division 1

**Daniel Ruiz,** General Manager

# **BOARD MEETING**

### **Agenda**

October 9, 2025, 6:00 p.m. 1887 Howard Street, Anderson (Council Chambers)

- 1. Call To Order
- 2. Flag Salute

### 3. Public Participation

Time is set aside for members of the public who wish to address the Board regarding matters within the District's jurisdiction. Individuals are requested to limit comments to a maximum of three minutes.

#### 4. Consent Items

- a. Payroll: Approve the Payroll Check Register for September 2025
- b. Electronic Federal Tax Payment System (EFTPS) & Automated Clearing House (ACH) Approve transactions for the Payroll Period 9/15/2025 and 9/30/2025
- c. Voided and/or missing checks for September 2025

### 5. Regular Business Items

- a. Minutes Approve the Minutes of the Regular Meeting on 9/11/25 and the Special Meeting on 9/3/25
- b. Financial Status Report for Year-to-Date through September 30, 2025
- c. Cash Disbursement Journal for September 2025

#### 6. New Business Items

- a. Review and Approve Main Canal Improvement Project Priorities
- b. Review and Approve Churn Creek Bottom Project Priorities
  - a. Reshape & Compaction Priorities
  - b. Pipe Repair Replacement Priorities
- c. Review and Approve Lateral Project Priorities
  - a. Lateral 33
  - b. Lateral 29
  - c. Lateral 21
- d. Review and Approve Irrigation Season Shutdown Recommendation
  - a. Main Canal
  - b. Churn Creek Bottom

#### 7. Other Business

- a. General Manager Report
- b. Operations Manager Report
  - Lateral 29 Outreach & Study Update
     2810 Silver Street, Anderson, CA 96007 | Phone: 530-365-7329 | Fax: 530-365-7623

### c. Committee Reports

- a. Budget
- b. Personnel
- c. Diversion Dam
- d. Assessment
- e. Strategic
- f. EAGSA
- g. SRSC

### 8. CLOSED SESSION -

- a. **Existing Litigation (Government Code § 54956.9(d)(1)).** United States of America v. 4.04 Acres of Land et al., U.S. Dist. Court, Eastern District of California, Case No. 2:23-cv-02800
- b. Conference with Legal Counsel Anticipated Litigation (Government Code § 54956.9(d)(4) One Case
- 9. Adjourn

#### 9/29/25 at 06:23:38.21 Page: 1

# Anderson Cottonwood Irrigation District Payroll Register For the Period From Sep 1, 2025 to Sep 30, 2025

	port order is by Check L	oute. Report is p	printed in Betain 1
Employee ID Employee Masked SS No Reference Date	Pay Type Pa	ny Hrs	Amount
25-04 Leedy, Harley XXX-XX-0578 20636 9/8/25	WO WO_OT	30.75 2.00	723.72
12A White, Teresa L. XXX-XX-9533 0407 9/15/25	Finance_Ma		2,218.11
21-09 Wilson, Kyle D. XXX-XX-2586 0408 9/15/25	Holiday Sick_Leave Vacation WO	8.00 36.00 25.00 19.00	1,825.40
22-03 Duncan, Benjamin XXX-XX-4453 0409 9/15/25	Ops_Manag		2,199.08
23 Passmore, Scott C. XXX-XX-4422 0410 9/15/25	Vacation	88.00	2,247.00
23-13 Brian, Johnson J. XXX-XX-4901 0411 9/15/25	Holiday WO WO_OT	8.00 88.00 8.00	2,339.79
24-02 Chabolla, Jordan B. XXX-XX-2772 0412 9/15/25	Holiday WO WO_OT	8.00 88.00 7.00	2,153.01
24-03 Ruiz, Daniel J. XXX-XX-5766 0413 9/15/25	General_Mg		5,180.49

#### Page: 2 9/29/25 at 06:23:38.23

# Anderson Cottonwood Irrigation District Payroll Register For the Period From Sep 1, 2025 to Sep 30, 2025

Filter Criteria includes: Rep	port order is by Check i	Date. Report is p	printed in Detail F
Employee ID Employee Masked SS No Reference Date	Pay Type Page 1	ay Hrs	Amount
24-05 Davis, Johna J. XXX-XX-4377 0414 9/15/25	Holiday WO WO_OT	8.00 88.00 9.50	2,112.84
25-01 Shults, Kaleb A. XXX-XX-1661 0415 9/15/25	WO WO_OT	88.00 17.50	2,229.17
25-03 Bell, Shawna M. XXX-XX-4563 0416 9/15/25	Office_Man	80.00	1,581.51
33 Vega, Phillip XXX-XX-1154 0417 9/15/25	Ops_Sup Overtime Holiday	80.00 2.00 8.00	2,280.91
23 Passmore, Scott C. XXX-XX-4422 0418 9/15/25	Holiday	8.00	234.08
21-11 Jensen, Jason A. XXX-XX-7425 20637 9/15/25	Equip_Oper Holiday Vacation	47.50 8.00 32.50	1,782.27
25-02 Jebens, Damon J. XXX-XX-0228 20638 9/15/25	WO WO_OT	82.00 5.50	1,768.06
23 Passmore, Scott C. XXX-XX-4422 20640 9/19/25	Vacation	51.31	1,346.28

# Anderson Cottonwood Irrigation District Payroll Register For the Period From Sep 1, 2025 to Sep 30, 2025

	port order is by check i		
Employee ID Employee Masked SS No Reference Date	Pay Type Pa	ay Hrs	Amount
12A White, Teresa L. XXX-XX-9533 0431 9/30/25	Finance_Ma		2,393.11
22-03 Duncan, Benjamin XXX-XX-4453 0432 9/30/25	Ops_Manag		2,199.08
23-13 Brian, Johnson J. XXX-XX-4901 0433 9/30/25	WO WO_OT	88.00 4.00	2,084.18
24-02 Chabolla, Jordan B. XXX-XX-2772 0434 9/30/25	WO WO_OT	84.00 6.00	1,916.82
24-03 Ruiz, Daniel J. XXX-XX-5766 0435 9/30/25	General_Mg		5,180.49
24-05 Davis, Johna J. XXX-XX-4377 0436 9/30/25	WO WO_OT	92.00 10.00	2,060.99
25-01 Shults, Kaleb A. XXX-XX-1661 0437 9/30/25	WO WO_OT	85.25 8.00	1,950.56
25-02 Jebens, Damon J. XXX-XX-0228 0438 9/30/25	WO WO_OT	90.00 3.50	1,863.97

# Anderson Cottonwood Irrigation District Payroll Register For the Period From Sep 1, 2025 to Sep 30, 2025

Employee ID Employee Masked SS No Reference Date	Pay Type	Pay Hrs	Amount
25-03 Bell, Shawna M. XXX-XX-4563 0439 9/30/25	Office_Man	88.00	1,729.27
33 Vega, Phillip XXX-XX-1154 0440 9/30/25	Main_Sup Overtime Vacation	87.00 6.50 1.00	2,546.95
21-11 Jensen, Jason A. XXX-XX-7425 20642 9/30/25	Equip_Oper Sick_Leave	79.25 8.00	1,766.45
Summary Total 9/1/25 thru 9/30/25	General_Mg Finance_Ma Vacation Ops_Manag Overtime Ops_Sup Equip_Oper Holiday Office_Man Sick_Leave Main_Sup WO WO_OT	8.50 80.00 126.75 56.00	57,913.59
Report Date Final Total 9/1/25 thru 9/30/25	General_Mg Finance_Ma Vacation Ops_Manag Overtime Ops_Sup Equip_Oper Holiday Office_Man Sick_Leave Main_Sup WO WO_OT	8.50 80.00 126.75 56.00 168.00 44.00 87.00 923.00 81.00	57,913.59

	Electronic Fe			Transactions (EFTPS)	
		Federal	Payroll Taxe	s	
Date	Payroll Period	Amount		Comments	
9/15/2025	8/26/25 - 9/09/25	\$10,157.14		EFTPS for P/R taxes	
9/30/2025	9/10/25 - 9/24/25	\$8,272.76		EFTPS for P/R taxes	
		Automated Cl	earing House	(ACH)	
			Payroll Taxes		
9/15/2025	8/26/25 - 9/09/25	\$2,215.31	dyron raxoo	ACH for P/R taxes	
9/30/2025	9/10/25 - 9/24/25	\$1,815.69		ACH for P/R taxes	
		Voided and/	or Missing Ch	necks	
Check #	Issued To:	Amount	Check Date Comments Date		
20641				Voided to order PR checks in QB	9/20/202
20639	Scott Passmore	1346.28	9/19/2025	Wrong hours uesd	9/19/202
0419-0430				voided payroll run / 1 check incorrect	9/30/202
	·			·	



### James Rickert, President, Division 5

Audie Butcher, Director, Division 2

### Ivar Amen, Vice President, Division 4

**Garrett Wallis**,
Director, Division 3

Ronnean Lund, Director, Division 1

**Daniel Ruiz,** General Manager

## **BOARD MEETING**

### **Draft Minutes**

September 11, 2025, 6:00 p.m. 1887 Howard Street, Anderson (Council Chambers)

1. Call To Order at 6:00 p.m.

Directors Present: Rickert, Amen, Wallis

**Directors Absent:** Butcher, Lund

Staff Present: Ruiz, White, Duncan, and BellSupervisor Chris Kelstrum led the Flag Salute

### 3. Public Participation

Time is set aside for members of the public who wish to address the Board regarding matters within the District's jurisdiction. Individuals are requested to limit comments to a maximum of three minutes.

Bridgette Grimson expressed appreciation to Dan for his assistance and apologized for a prior phone interaction involving her husband. She thanked the district for resolving a recent issue with a grate.

- The primary concern presented was on behalf of her mother-in-law, a long-time resident and cattle rancher on Lateral 29, who has been experiencing insufficient water delivery to irrigate her field.
- Due to the lack of water, her pasture has dried up. She has reduced her cattle from 65 to 45 head. The feed is running low, and the field is now overtaken by weeds instead of grass.
- The issue was first noticed in June and partially addressed after meeting with the ditch tender, but water levels declined again.
- Despite contacting appropriate personnel, no lasting resolution was achieved until a recent conversation with Dan led to improved water flow.
- The speaker requested that this issue be formally added to a future board meeting agenda for resolution.

Jeff Parman, a resident of 22903 Adobe Road, expressed ongoing frustration with the inconsistent water delivery throughout the irrigation season.

- Key concerns included: Missed water cycles early in the season with no prior notification. A major canal break was only discovered after the resident contacted the office.
- After a temporary improvement, water delivery declined again due to canal draining for vegetation management.
- A leak repair near the property was only partially completed (100 ft of a 200 ft section), and the issue reoccurred after the next cycle.

- The resident reported receiving only half to three-quarters of a head of water, impacting pasture growth, and forcing early relocation of cattle to dry pasture.
- Communication issues were emphasized: Lack of proactive alerts about service disruptions. Frustration
  with the ditch tender's dismissive responses to concerns. Positive feedback was given to a weekend
  replacement ditch tender, Kaleb, for being responsive and accommodating.
- The speaker urged the district to improve both water consistency and communication practices, especially for the remainder of the season and into next year.

Bill Gifford - Reported this season as the worst he has experienced, citing inconsistent water delivery after a typical first cycle. One strong flow showed that adequate delivery is possible, but it was not sustained.

He had to skip irrigation on an 8-acre field for a month, leading to poor grass and weed growth. His pond showed minimal refill despite extended water flow. Additional water purchases yielded less than expected, and erosion risks complicated water management.

Bill received only 43% of his contracted water, confirmed by his wife and engineer Susan Goodwin. He also faced:

- Unscheduled water reallocation by a neighbor.
- Reduced pasture quality, causing livestock removal.
- Frequent valve adjustments due to low flow.
- Lack of transparency in water allocation and poor communication with ditch tenders.

He emphasized the need for better water management and accountability, noting similar issues among neighbors.

Buddy Pettyjohn - Expressed staunch support for previous speakers regarding ongoing issues with water delivery on Line 29, stating this has been the worst irrigation season he has experienced.

- Key concerns included: Extended irrigation cycles: Promised 14-day cycles but have been stretched to 17–17.5 days, causing significant disruption. Noted visible fluctuations in water head and questioned why water delivery varies so drastically. Expressed frustration over receiving water at night instead of daytime and questioned whether this was punitive.
- Historical comparison: Recalled better irrigation service prior to district upgrades and funding, questioning current performance.
- Suggested remedies: Proposed temporarily shutting off pumps to Churn Creek to highlight the impact of delayed cycles. Asked the board to consider a 20% refund for affected users over the past two years due to reduced water access.

### **Board Response**

- Board members acknowledged the seriousness of the issues on Line 29, stating the current level of service is unacceptable. Apologies were issued to affected residents, with recognition of their frustration.
  - The board committed to: Addressing Line 29 as a priority during the upcoming off-season. Evaluating appropriate actions, including potential compensation, though no decisions were made during the meeting. Working collaboratively to resolve infrastructure and service problems.

#### 4. Consent Items

- a. Payroll: Approve the Payroll Check Register for August 2025
- b. Electronic Federal Tax Payment System (EFTPS) & Automated Clearing House (ACH) Approve transactions for the Payroll Periods August 15, 2025, and August 29, 2025
- c. Voided and/or missing checks for August 2025

VP Ivar made the motion to approve Consent Items; Director Wallis seconded the motion. No public comment. Vote 3-0 approved.

#### 5. Regular Business Items

- a. Minutes Approve the Minutes of the Regular Meeting on August 14, 2025
- b. Financial Status Report for Year-to-Date through August 31, 2025
- c. Cash Disbursement Journal for August 2025

Director Wallis made the motion to approve Regular Business Items; VP Ivar seconded the motion. No public comment. Vote 3-0 approved.

#### 6. New Business Items

- a. Review and Approve Resolution CDAA-2025-07: Cal OES Designation of Applicant's Agent Resolution, Non-State Agencies
- b. Review and Approve Proposal for Engineering Services for the Replacement of Damaged Lining at the North Hill St. Canal Reach, Anderson California
- c. Main Canal Capital Improvement Project Priorities and Pricing Update
- d. Churn Creek Bottom Project Priorities
  - a. Reshape & Compaction Priorities
  - b. Pipe Repair and Replacement Priorities
- e. Lateral Project Priorities
  - a. 33, 29, & 21

Item 6a: Review and Approval of Resolution CDAA2025-07 - Designation of Applicant's Agent for Non-State Agencies

- The board reviewed Resolution CDAA2025-07, a formal designation of the applicant's agent related to February flood events.
- The resolution is a procedural requirement following the Governor's declaration of a state of emergency in late July, with Shasta County having acted early in the process.
- The designation helps initiate project-related processes and may remain valid for several years.
- Due to staffing changes, including a new office manager, the resolution requires updating and submission.
- Deadline for submission is September 22 to ensure continued coordination with Shasta County.
- A motion to approve the resolution was made and seconded.
- No public comments were received.

VP Ivar made the motion to approve Resolution; Director Wallis seconded the motion. No public comment. Vote 3-0 approved.

Item 6b: Review and Approval of Engineering Proposal – Northville Canal Reach (Anderson)

- The board reviewed a previously seen proposal for engineering services related to the replacement of a damaged lane at the Northville Canal Reach.
- Total proposal cost: \\$60,000, broken down into three phases:
  - 1. Hydrologic Evaluation \\$16,000
  - 2. Design & Replacement \\$22,000
  - 3. Construction Support \\$22,000
- Minor wording edits were suggested to clarify the outlet structure's function, replacing "pasture" with "storm water and watershed" to better reflect actual conditions.
- The hydrologic evaluation is prioritized due to lead time and urgency following recent flood events. Remaining phases will be revisited at a future meeting when the full board is present.
  - Discussion included: Clarification that the canal overtopping was due to a disconnected berm.
     No need for landowner approval due to existing easement, though outreach is planned.
     Potential for further investigation outside the current scope.

Director Wallis made the motion to approve Hydrologic evaluation only; VP Ivar seconded the motion. No public comment. Vote 3-0 approved.

Item 6C, D and E: Main Canal Capital Improvement Project, Churn Creek Bottom and Lateral Projects

- Main Canal, Lateral 29, Pickup Ditch: Discussion continued for priority upgrades. No formal action taken; board to await committee recommendations. Work may begin as early as Nov. 1, pending dry conditions and contractor availability.
- Project Estimates: Staff presented bids from two contractors for three segments:
  - Priority 1 (11,000 ft): \\$990K-\\$996K
  - Priority 2 (3,400 ft): \\$374K-\\$414K
  - Priority 3 (200 ft): \\$230K-\\$243K
     Total: \\$1.59M-\\$1.65M. Discounts possible if all segments awarded. Final scope expected mid-October.
- Lateral 29 & Pipe Issues: Historical infrastructure problems noted. CCTV inspections planned for 1,800
  ft to assess pipe conditions. Long-standing leaks and obstructions identified; some repairs may be
  delayed due to access.
- Pickup Ditch (Area 5): Multiple leaks and structural issues reported. Plan to re-pipe degraded sections and extend piping based on material availability. Significant water loss documented.
- Landowner Access & Easements: Staff faced disputes over ditch access. Work paused pending proper
  permits. Proposal made to standardize fencing policies and clarify easement boundaries to avoid future
  conflicts.
- Operational Challenges: Water delivery delays and rotation issues persist, especially in Lateral 29. Staff evaluating siphon installation and infrastructure upgrades. Vestra consulting on feasibility.
- Personnel & Oversight: Early season staffing issues acknowledged. Recommendation to re-engage experienced staff (e.g., Phil) for field oversight and training. Suggestion to create a ditch tender manual.

- Public Feedback: Irrigators voiced concerns over poor water delivery, rigid scheduling, and lack of communication. Calls for more frequent engagement, an action plan for Lateral 29 and Pickup Ditch, and better coordination among neighbors.
- Next Steps: Staff to develop and present an action plan at the next meeting. Future meetings involving key decisions should be held during regular sessions to ensure public participation.

#### 7. Other Business

- a. General Manager Report
- b. Operations Manager Report
- c. Committee Reports
  - a. Budget
  - b. Personnel
  - c. Diversion Dam
  - d. Assessment
  - e. Strategic
  - f. EAGSA
  - g. SRSC

Item 7a: General Manager's Report – September – included in the Board packet

Item 7b: Operations Manager Report

#### Water Operations

- Main Canal: Flow reduced from 240 to ~210 CFS; algae bloom affecting volume. Crowley Gulch holding 70–90 CFS. Area 5 laterals add ~20 CFS when active.
- C Creek: Stable at 55 CFS (3 pumps); drops to ~33 CFS with 2 pumps.
- River Flows: Ramping down to 7600 CFS for conservation; impacts Turn Creek pump pressure.
- Rain Impact: Brief storm caused overnight spillage at Crowley.
- Season Wrap-Up: Most laterals ending around Sept 20; full shutdown by Oct 31. Final splash planned for Lateral 29 and pickup ditch.

### Infrastructure & Maintenance

- Repairs: Fish screens/pulleys restored; pipe leaks exposed and redirected. Grill installations are ongoing.
- Emergencies: Beaver dam removed; tree cleared from Lateral 3; golf course leak resolved.
- Drainage Issues: Temporary levee redirected water; pipe repair/replacement proposed.
- Ditch Work: Reactive vegetation clearing; excavator use tracked.
- Cow issue, temporary metal done, grill list made, and improvements planned.

### **Projects & Funding**

- NRCS Project: Approved after 3+ years; planning underway for materials, labor, and reimbursement.
- Contractor Estimates: Lateral reshaping at \$25-\$35/ft; pipe materials priced separately.
- NRCS Bulk Pricing: Potential discounts for truckload purchases.

### Spray Program

- Application Timing: Late winter/early spring, mid-June, optional fall.
- Cost Breakdown:
  - Contractors: \$160/acre
  - District Staff: \$124/acre (labor, chemicals, maintenance)
- Equipment: 200–300 gallons/day capacity; ~146 acres in main canal.
- Notes: Costs may rise due to limited access and terrain.

#### Canal Shutdown Recommendation

- Most scheduled laterals (e.g., 33, 35) will naturally end around October 20. Unscheduled laterals (e.g., 29, 33) may continue running until water is unavailable.
- Recommendation: shut down main around the 20th, allow 3–5 days for water to run out, and let the system taper off organically.

#### Next steps

- Finalize Dam Removal: possibly scheduled for Nov 1, first Monday in November. Board approval for next Board Meeting.
- Board/Public Support: Appreciation for emergency response and transparency.
- Finalizing proposals, calibrating spray coverage, and preparing for off-season work.

#### **Board & Public Feedback**

- Public and board members expressed appreciation for: Emergency response to electrical hazard and water lowering. Continued commitment to safety and equitable water delivery.
- Transparency and thoroughness in planning and reporting.
- 8. Adjourned Public session at 7:47 pm
- 9. CLOSED SESSION started at 7:50 pm
  - a. **Existing Litigation (Government Code § 54956.9(d)(1)).** United States of America v. 4.04 Acres of Land et al., U.S. Dist. Court, Eastern District of California, Case No. 2:23-cv-02800
  - b. Conference with Legal Counsel Anticipated Litigation (Government Code § 54956.9(d)(4) One Case Closed session adjourned at 8:55 p.m. no action
- 10. Adjourn meeting adjourned at 8:57 p.m.



### James Rickert, President, Division 5

Audie Butcher, Director, Division 2

### Ivar Amen, Vice President, Division 4

**Garrett Wallis**, Director, Division 3

### Ronnean Lund, Director, Division 1

**Daniel Ruiz,** General Manager

# SPECIAL BOARD MEETING

### **Draft Minutes**

September 3, 2025, 9:00 a.m.

1887 Howard Street, Anderson (Council Chambers)

1. Called To Order at 9:01 am by James Rickert

**Directors Present**: Garrett Wallis, James Rickert, Ronnean Lund, Ivar Amen

**Directors Absent:** Audie Butcher

Staff Present: Dan Ruiz and Shawna Bell

2. Flag Salute – led by Garrett Wallis

### 3. Public Participation

Time is set aside for members of the public who wish to address the Board regarding matters within the District's jurisdiction. Individuals are requested to limit comments to a maximum of three minutes.

James Rickert - no public comments

#### 4. Old Business

a. Presentation from Danny Kerns, PE Provost & Pritchard on 2<sup>nd</sup> Main Canal Lining Repair - lining repair project, covering approximately 400 feet of canal located upslope from a residential area impacted by groundwater intrusion in spring/summer 2023.

Initial Work & Site Conditions: Vegetation removal and dewatering were conducted. Saturated and unsuitable subgrade materials were encountered, requiring stabilization.

### Implemented Measures:

- Subgrade Stabilization: Installed geogrid beneath six inches of compacted base rock to create a stable foundation.
- French Drain System: Constructed a one-foot deep and wide trench lined with geotextile fabric and filled with drain rock. Designed to collect groundwater and direct it to pressure relief valves.
- Pressure Relief Valves: Nine Waterman-brand valves installed via vertical perforated PVC pipes embedded in the French drain. Valves relieve groundwater pressure beneath the liner and are located on the water side of the canal.

Post-Installation Observations: A significant heave (~60 feet long) was observed in the canal bottom after the irrigation season, with cracking along most of the reach. The heave is attributed to vertical groundwater pressure (buoyancy) beneath the liner.

Engineering Evaluation & Recommendations: A buoyancy analysis was conducted comparing upward water pressure with the downward force of the liner and concrete. Conservative assumptions were used, including average valve elevation and valve activation pressure (0.29 PSI). Uplift pressures ranged from 10 to 40 PSI.

Recommended Solution: Add concrete ballast to increase downward force and achieve a safety factor of 1.3 to 1.5. This avoids destructive modifications to the intact liner.

#### Additional Discussion Points:

- Liner Integrity: The liner includes an 840-mil HDPE geomembrane with geotextile on both sides. Despite visible cracks, only minimal seepage was observed, suggesting the liner remains intact.
- Seam Concerns: Seams are considered the most vulnerable points. Observed leakage is minimal and not indicative of major failure.
- Elasticity & Manufacturer Specs: Questions were raised about the membrane's elasticity and long-term integrity. The engineering team believes the liner is still performing effectively.
- Future Inspections: Further evaluation will be conducted after the irrigation season to reassess liner condition and validate the ballast solution.

### Alternative Considerations & Design Details:

- Hydro Boring Option: Explored the idea of installing horizontally drilled perforated pipes to relieve groundwater pressure. Ultimately not pursued due to limited effectiveness at the canal bottom.
- Concrete Fill Design: Plans include varying depths of concrete fill, maintaining a minimum of 3 inches. Fill will be shaped to avoid creating backwater or hydraulic issues. Cross-sections were developed to show fill quantities at valve locations.
- Bonding Measures: Contractors will trench 1.5–2 inches at upstream/downstream edges to key new
  concrete into existing lining. Existing concrete will be pressure-washed to remove debris and promote
  bonding.
- A longer fiber mix will be used to reduce shrinkage cracking. Fiber cost details are to be provided by the concrete supplier.

### 5. Closed Session – moved into closed session at 9:47 am

a. Conference with Legal Counsel – Anticipated Litigation (Government Code § 54956.9(d)(4) One Case – closed session adjourned 10:35 am - no action

#### 6. New Business

a. Review and Discuss Approving Engineering Services for the Replacement of Damaged Lining at the North Hill St. Canal Reach (Danny Kerns to Present)

#### Summary:

- A winter storm caused overtopping and damage to the North Hill Street canal liner, compromising about half of the reach.
- Temporary slurry repairs were made for the current irrigation season.
- A full replacement is proposed, with design considerations to prevent future overtopping and flooding.

- A hydrologic/hydraulic study is recommended to evaluate stormwater inflow, basin storage capacity, and canal bank elevation requirements. The study will inform design options, including potential emergency spillway integration.
- Estimated cost for Engineering work is \$60,000. Board expressed interest in proceeding with the hydrologic evaluation as the first phase, pending cost proposal. Final proposal to be reviewed at the next board meeting on September 11.
  - b. Review and Discuss Draft Main Canal & Churn Creek Flow Measurement Program (Danny Kerns to Present)

#### Summary:

A two-phase study was conducted to assess water loss along the main canal and Churn Creek bottom.

- Phase 1: Desktop analysis using soil data, hydraulic conductivity, evapotranspiration (ET), groundwater-dependent ecosystems, and SAGBI index. Eight high-risk reaches were identified.
  - Seasonal groundwater surveys showed the canal may gain water in winter and lose it in summer, informing future water-saving strategies.
  - ET data and field observations confirmed areas of seepage, especially near Panorama Point and Clear Creek.
- Phase 2: Flow measurements using acoustic Doppler equipment will quantify actual water loss.
   Measurements planned for fall, spring, and possibly summer to capture seasonal variation.
  - Coordination with operations is needed to ensure consistent conditions across seasons and valid comparisons.

Goal: Support targeted maintenance and water efficiency improvements using data-driven insights.

### 7. Meeting adjourned at 11:15 am.

		son Cottonwood I 2025 Financial Sta		t		
		nth Ending Septen				
		<u> </u>				
		Revenues	3			
Account	Budget Item	Month	Year		Percent	Budget
Number		То	То	Approved	Used	Over/Under
		Date	Date	Budget		
		General				
4110	Permits	\$0	\$3,359	\$0	0%	(\$3,359
4111	Water Sales / Prior Year	\$0	\$0	\$0	0%	\$0
4112	Water Sales / Business	\$8,143	\$8,643	\$8,143	106%	(\$500
4114	Water Sales / Irrigation	\$0	\$714,530	\$718,000	100%	\$3,470
4115	Water Transfer / CVP	\$0	\$591,066	\$606,161	98%	\$15,095
4117	Water Transfer / Base Supply	\$0	\$75,625	\$75,630	100%	\$5
4934	Penalty Revenue	\$0	\$0	\$0	0%	\$0
4971	Surplus Equipment Sales	\$0	\$0	\$0	0%	\$0
4980	Misc. Revenue	\$0	\$10,080	\$1,500	672%	(\$8,580
4984	Drainage Revenue	\$0	\$0	\$0.00	0%	\$0
4991	Contract/Project Income	\$0	\$0	\$0.00	0%	\$0
	Sub-Total	\$8,143	\$1,403,303	\$1,409,434	100%	\$6,131
Account	Budget Item	Month	Year	2025	Percent	Budget
Number	, and the second second	То	То	Approved	Used	Over/Under
		Date	Date	Budget		
		Property Tax & I	nterest			
4920	Interest / Investment Revenue	\$129,789	\$457,091	\$331,693	138%	(\$125,398)
4930	Prop. Taxes / Shasta	\$92	\$301,971	\$645,000	47%	\$343,029
4931	Prop. Taxes / Tehama	\$0	\$23,158	\$52,800	44%	\$29,642
	Sub-Total	\$129,881	\$782,220	\$1,029,493	76%	\$247,273
	T	4400.004	<b>A</b> 0.405.500	<b>\$0.400.007</b>	000/	4050.404
	Total Revenues	\$138,024	\$2,185,523	\$2,438,927	90%	\$253,404
		son Cottonwood I		t		
		2025 Financial Stanth Ending Septen				
		Expenditur	es			

Account	Budget Item	Month	Year	2025	Percent	Budget
Number		То	То	Approved	Used	Over/Under
		Date	Date	Budget		
		Salaries & Be	nefits			
5010	Reg. Salaries (Admin)	\$24,614	\$205,339	\$351,478	58%	\$146,139
5012	Overtime (Admin)	\$0	\$0	\$0	0%	\$0
5014	Retirement (Admin)	\$672	\$11,114	\$17,805	62%	\$6,691
5015	Social Security (Admin)	\$1,261	\$12,807	\$21,792	59%	\$8,985
5016	Workers Comp. (Admin)	\$1,865	\$14,346	\$12,002	120%	(\$2,344)
5017	U.I. Insure. (Admin)	\$0	\$1,029	\$1,739	59%	\$710
5018	Medicare (Admin)	\$295	\$2,995	\$5,096	59%	\$2,101
5019	Health Insurance (Admin)	\$0	\$23,532	\$50,357	47%	\$26,825
5110	Reg. Salaries (T&D)	\$48,453	\$432,387	\$604,084	72%	\$171,697
5111	Temp Labor/Veg Management	\$13,328	\$37,627	\$0	0%	(\$37,627)
5112	Overtime (T&D)	\$3,617	\$40,099	\$48,327	83%	\$8,228
5114	Retirement (T&D)	\$11,970	\$36,394	\$46,189	79%	\$9,795
5115	Social Security (T&D)	\$4,216	\$31,704	\$39,954	79%	\$8,250
5116	Workers Comp. (T&D)	\$6,976	\$63,045	\$110,292	57%	\$47,247
5117	Unemployment Ins. (T&D)	\$0	\$3,430	\$4,803	71%	\$1,373
5118	Medicare (T&D)	\$590	\$6,698	\$9,344	72%	\$2,646
5119	Health Ins. (T&D)	\$746	\$97,932	\$138,122	71%	\$40,190
	Sub-Total	\$118,603	\$1,020,478	\$1,461,384	70%	\$440,906
	1				1	
	Anders	son Cottonwood I	rrigation Distric	ct		
		025 Financial Sta				
		nth Ending Septer				
		υ,	•			
Vocarint	Dudget Item	Expenditur	es Year	2025	Dorcont	Dudast
Account	Budget Item	Month To			Percent	Budget
Number		Date	To Date	Approved Budget	Used	Over/Under
		Date	Date	Duugei		

		Administration	on			
6001	Medical Exp./Supplies	\$1,269	\$1,606	\$2,200	73%	\$594
6002	Travel / Training Expense	\$0	\$1,404	\$8,000	18%	\$6,596
6003	Office Supplies/Expense	\$0	\$7,974	\$14,000	57%	\$6,026
6004	Office Equip. & Maintenance	\$0	\$0	\$2,000	0%	\$2,000
6005	Association Dues	\$265	\$15,434	\$20,000	77%	\$4,566
6006	Public Notices	\$0	\$0	\$500	0%	\$500
6007	Election Expense	\$0	\$0	\$0	0%	\$0
6008	Legal Fees / Expense	\$6,541	\$80,285	\$80,000	100%	(\$285
6009	SRSC Corporation	\$0	\$20,822	\$21,000	99%	\$178
6010	Maintenance Agreements	\$2,595	\$19,492	\$31,000	63%	\$11,508
6012	Vehicle Insurance	\$0	\$15,527	\$18,200	85%	\$2,673
6013	Management Expense Acct.	\$54	\$414	\$1,000	41%	\$586
6014	Liability Claims	\$0	\$0	\$0	0%	\$0
6015	Property/Liability Insurance	\$0	\$82,781	\$90,000	92%	\$7,219
6016	Permit Fees	\$0	\$17,837	\$12,000	149%	(\$5,837
6017	County Taxes/Assessments	\$0	\$20,471	\$8,200	250%	(\$12,271
6018	Consultant Services	\$0	\$11,292	\$25,000	45%	\$13,708
6019	Audit/Accounting Services	\$0	\$0	\$8,000	0%	\$8,000
6020	Web Site	\$0	\$0	\$0	0%	\$0
6021	Safety/Incentive Awards	\$0	\$0	\$500	0%	\$500
6023	Utilities	\$1,204	\$18,238	\$24,000	76%	\$5,762
	Sustainable Groundwater					
6027	Management Acct. (SGMA)	\$0	\$0	\$0	0%	\$0
		\$11,928	\$313,577	\$365,600	86%	\$52,023

### Anderson Cottonwood Irrigation District 2025 Financial Status Report Month Ending September 30, 2025

Account Number	Budget Item	Month To	Year To	2025 Approved	Percent Used	Budget Over/Under	
		Date	Date	Budget			
		General Mainte					
7000	Fuels	\$6,890	\$45,106	\$70,000	64%	\$24,894	
7001	Equipment Rents & Leases	\$0	\$7,029	\$15,000	47%	\$7,971	
7002	Light Vehicles	\$1,933	\$13,698	\$15,000	91%	\$1,302	
7003	Heavy Vehicles	\$0	\$9,905	\$8,500	117%	(\$1,405)	
7004	Light Equipment	\$94	\$5,433	\$2,500	217%	(\$2,933)	
7005	Heavy Equipment	\$0	\$7,141	\$10,000	71%	\$2,859	
7006	Hand Tools	\$0	\$249	\$2,500	10%	\$2,251	
7007	Personal Supplies & Equipment	\$0	\$2,955	\$12,000	25%	\$9,045	
7008	Maintenance Supplies	\$1,289	\$10,197	\$25,000	41%	\$14,803	
7009	Building/Yard Maintenance	\$420	\$4,974	\$12,000	41%	\$7,026	
7010	Small Tools & Equipment	\$321	\$3,284	\$5,500	60%	\$2,216	
7011	Engineering Services	\$3,833	\$43,477	\$25,000	174%	(\$18,477)	
	Sub-Total	\$14,780	\$153,448	\$203,000	76%	\$49,552	
	Canal Maintenance & Operations						
8000	SCADA Maintenance	\$104	\$4,439	\$5,000	89%	\$561	
8001	Diversion Facilities Maint.	\$5,279	\$12,547	\$25,000	50%	\$12,453	
8002	Contracted Services	\$1,472	\$26,120	\$20,000	131%	(\$6,120)	
8003	Chemicals	\$0	\$13,179	\$19,000	69%	\$5,821	

8004	Canal Maintenance & Exp.	\$3,099	\$58,480	\$175,000	33%	\$116,520
8005	Pump Maintenance	\$423	\$9,874	\$15,000	66%	\$5,126
8006	Utilities / Pumping	\$27,826	\$137,192	\$140,000	98%	\$2,808
8007	Project Water Costs / USBR	\$0	\$257,097	\$365,343	70%	\$108,246
8008	Water Rights Protection	\$8,781	\$32,816	\$75,000	44%	\$42,184
8010	Water Transfer / Base Supply	\$0	\$0	\$0	0%	\$0
8019	Tree Removal	\$0	\$59,120	\$75,000	79%	\$15,880
	Sub-Total	\$46,984	\$610,864	\$914,343	67%	\$303,479

# Anderson Cottonwood Irrigation District 2025 Financial Status Report

Month Ending September 30, 2025

	Balance Sur	mmary			
	Month	Year	2025	Percent	Budget
	То	То	Approved	Used	Over/Under
	Date	Date	Budget		
Total Expenditures	\$192,295	\$2,098,367	\$2,944,327	71%	\$845,960
		4			
Total Revenues	\$138,024	\$2,185,523	\$2,438,927	90%	\$253,404
Operational Not Income	(¢E4.074)	\$87,156	(\$505,400)		
Operational - Net Income	(\$54,271)	\$87,130	(\$505,400)		
Non-Operational - Capital Costs	(1,129)	(2,035,741)	(1,711,300)		
Non operational Supital Social	(1,123)	(2,000,741)	(1,711,000)		
Net Income w/Capital (cash flow)	(\$55,400)	(\$1,948,585)	(\$2,216,700)		
	(, , , , ,	(, , , , ,	(, , , , , , , , , , , , , , , , , , ,		
Other Income - DPP Funding		\$14,214,346			
DPP True Up		\$ 110,608			
Total Cash Flow with All Activity		\$12,376,369			•
	Capital Improv	omont			

Capital Improvement 2025 Month Percent Budget Year То То Approved Used Over/Under Date Date Budget 1112 Land \$0 \$0 \$0 0% \$0 \$0 0% 1114 Pumps \$0 \$0 \$0 \$30,015 1116 Trans & Distribution System \$0 \$19,985 \$50,000 40% 1117 Equipment (Machinery) \$0 \$0 0% \$0 \$0 1118 Auto & Trucks \$0 \$69,458 \$41,000 169% (\$28,458)1119 Buildings \$0 \$0 0% \$0 \$0 1120 Office Furniture & Equipment \$0 \$9,924 \$9,300 107% (\$624)1123 Yard Improvement \$0 0% \$0 \$0 \$0 1124 Canal Lining & Pipe \$1,129 \$1,920,842 \$1,591,000 121% (\$329,842) 1125 Canal Safety Project \$0 \$0 \$0 0% \$0 1126 Main Canal Metering \$0 \$0 0% \$0 \$0 1127 Main Dam Improvement \$0 0% \$0 \$0 \$0 1132 Fish Screens \$0 \$0 \$0 0% \$0 1133 Fish Ladders \$0 \$0 \$0 0% \$0

1134 SCADA Equipment	\$0	\$15,532	\$20,000	78%	\$4,46
1135 Groundwater Program	\$0	\$0	\$0	0%	\$(
Total	\$1,129	\$2,035,741	\$1,711,300	119%	(\$324,44
An	nderson Cottonwood I		t		
	2025 Financial Sta				
	Month Ending Septen	nber 30, 2025			
	Breakdown of Re	eserves			
L.A.I.F.	\$4,494,494				
TCB Checking	\$271,640				
Petty Cash	\$100				
Imprest Cash	\$200				
RBC Investments	\$17,037,522				
Total Cash	\$21,803,956				
-	·				

### For the Period From Sep 1, 2025 to Sep 30, 2025

Date	Check #	Account ID	Line Description	Debit Amount	Credit Amount
9/2/25	31996	5119	September insurance for	746.00	
		1308	Kyle Wilson N.C.G.T. Security Fund		746.00
9/5/25	31997	8001	repair on both pulley	3,672.50	
		1308	systems on fish screens Bloom's Mobile Truck		3,672.50
			Equip. & Repair		
9/5/25	31998	6001	pre employment testing (2) employees, (1) employee	1,119.00	
			RTD testing, SAP set up for (1) employee		
		1308	Compliance Associates		1,119.00
9/5/25	31999	7000	diesel/gasoline fuel for August	6,989.69	
		1308	Flyers Energy, LLC		6,989.69
9/5/25	32000	7008	wire brush, paint mixer, bulbs	112.04	
		1308	Ace Payment Processing		112.04
9/5/25	32001	8005	syn oil for dump truck, gloves	85.39	
		1308	JMB Oil		85.39
9/5/25	32002	5111	temp labor-2 employees	2,641.76	
		1308	for 2 weeks K S Staffing Solutions Inc.		2,641.76
9/5/25	32003	7008	5 pike poles/trash forks	327.76	<b>.</b>
		1308	BDI		327.76
9/5/25	32004	6010 1308	monthly maintenance plan Obsidian IT	969.06	969.06
9/5/25	32005	7008	24" coupler	67.89	
		1308	Oldcastle Infrastructure		67.89
9/5/25	32006	8004	plywood blows, quikcrete concrete, screws	180.21	
		1308	Payless Building Supply		180.21
9/5/25	32007	7008 1308	drinking water for shop Primo Brands	116.49	116.49
9/5/25	32008	7011	Main Canal Water Loss	360.65	
,, U, <b>2</b> U	2200	1124 1308	Hill st. repair Provost & Pritchard	1,128.80	1,489.45
9/5/25	32009	8006	Churn Creek	21,343.18	1,407.43
715143	32007		pumps/August		
		8006	Progress Drive pump/August	449.26	
		8000 1308	SCADA/August City Of Redding	86.00	21,878.44
9/5/25	32010	7010	check and repair 3" pump	320.52	252.55
		1308	Stroup's Power Equipment, INC		320.52
9/5/25	32011	2222	union dues for September	721.00	
		1308	Teamsters Local No. 137		721.00
9/5/25	32012	6010	State Fee for Regulatory cost	1,145.87	
		1308	Underground Service Alert		1,145.87
9/5/25	32013	5014	Pension for August/Admin	156.80	
		5114	Pension for August/T&D	3,073.28	

### For the Period From Sep 1, 2025 to Sep 30, 2025

Date	Check #	Account ID	Line Description	Debit Amount	Credit Amount	
		1308	Western Conf. Team. Pension		3,230.08	
9/11/25	33007	5111	temp labor for 4 employees for 2 weeks	5,860.36		
		1308	K S Staffing Solutions Inc.		5,860.36	
9/11/25	33008	8004	Invoice 2144820,5305,5426,5757, pea gravel, concrete,hitch rental	1,053.19		
		1308	Loucks Landscape Supply		1,053.19	
9/11/25	33009	7002	2022 F150 pickup oil change	136.51		
		7002 7004	2023 F150 oil change 2022 F150 oil change	115.19 93.64		
		7004	2016 F150 oil change	73.91		
		7002	past due amount	0.80		
		1308	Nor Cal Rentals	0.00	420.05	
9/11/25	33010	8000	SCADA	17.25		
		1308	Pacific Gas & Electric		17.25	
9/11/25	33011	7002	tires for 2023 F150 pickup	1,432.68		
		1308	Les Schwab Tires		1,432.68	
9/11/25	33012	7002	CM con renain	173.97		
9/11/23	33012	8001	GM car repair grip poles, brush, telepole, work on fish screens	1,316.90		
		7003	repair of dump truck	1,026.69		
		6010	Linx up, Fat Cow, Adobe, Grammerly	479.93		
		6003	copy paper, staples, usb charger, iphone caes,	639.53		
		1308	Tri Counties Bank		3,637.02	
9/11/25	33013	6023	garbage for office/August	162.42		
		8004 1308	dumpster for August Waste Management	1,391.76	1,554.18	
0/10/05	22000	0004		45.4.10		
9/12/25	33000	8004 1308	barbwire (4) Anderson Farm & Yard	474.10	474.10	
9/12/25	33001	6003	Name Plates (3)	38.33		
<i>y,</i> 12, 20	22001	1308	Anderson Trophies and Awards	30,30	38.33	
9/12/25	33002	2224	withholding for 9/15/25	100.00		
		1308	pay period CA State Disbursement		100.00	
		1300	Unit		100.00	
9/12/25	33003	2224	withholding for 9/15/25	350.00		
			pay period			
		1308	CA State Disbursement Unit		350.00	
9/12/25	33004	6003	copies for August	170.59		
<i>3,</i> 12, 20	2200.	1308	Carrel's Office Machines	1,0,0,	170.59	
9/12/25	33005	5114	withholding for 9/15/25	165.53		
		2226	payroll retirement for 9/15/25 pay	250.00		
		1308	period Edward Jones - Ben Swim		415.53	
9/12/25	33006	5114	retirement for 9/15/25	515.65		
			payroll	213.00	E1E / F	
		1308	Edward Jones - Ben Swim		515.65	
9/16/25	33014	6023	waster for office/shop for	21.73		

### For the Period From Sep 1, 2025 to Sep 30, 2025

Date	Check #	Account ID	Line Description	Debit Amount	Credit Amount	
		1308	August City Of Anderson		21.73	
9/16/25	33015	6001	pre employment testing (2 employees)	150.00		
		1308	Burch Physical Therapy		150.00	
9/16/25	33016	6008	General - August	5,228.17		
		8008 6008	Water Rights - August Canal Float - August	278.13 1,312.75		
		1308	Minasian Law LLP		6,819.05	
9/16/25	33017	8001	Diversion facilities - August	289.75		
		1308	City Of Redding		289.75	
9/16/25	33018	8008	2019 PCFFA Lit - ACID - August	302.59		
		8008 1308	NRDC - August Somach Simmons & Dunn	200.31	502.90	
				=	302.90	
9/16/25	33019	8002 1308	Invoice 12698 for Ishi The Embroidery Shope	1,471.88	1,471.88	
9/22/25	33007V	5111	temp labor for 4		5,860.36	
		1308	employees for 2 weeks K S Staffing Solutions Inc.	5,860.36		
9/25/25	33030	6023	power for August, office & shop	1,020.05		
		8006	power for August, Well #1	43.00		
		8006	power for August, Anderson Creek	1,274.30		
		8006	power for August, well #2	27.47		
		8006	power for August, Perrys pond	367.65		
		8006	power for August, Dymesich pond	1,892.34		
		8006 1308	power for August, Lat #46 Pacific Gas & Electric	2,429.20	7,054.01	
9/26/25	33020	2224	Withholding for 9/30/25 payroll period, JJ	350.00		
		1308	CA State Disbursement Unit		350.00	
9/26/25	33021	2224	withholding for 9/30/25	100.00		
		1308	payroll period, JD CA State Disbursement		100.00	
			Unit			
9/26/25	33022	5014	+Retirement for 9/30/25	515.63		
		1308	pay period Edward Jones - Ben Swim		515.63	
9/26/25	33023	2226	withholding for 9/30/25	250.00		
		5114	pay period Retirement for 9/30/25	165.53		
		1308	pay period Edward Jones - Ben Swim		415.53	
9/26/25	33024	6003	Business cards for two	140.08		
		1308	employees Harvest Printing		140.08	
9/26/25	33025	5111	Temp labor for 3 employees, invoices #305299,650,684,733,789 ,843	10,686.08		
		1308	K S Staffing Solutions Inc.		10,686.08	
				3,472.16		

### For the Period From Sep 1, 2025 to Sep 30, 2025

Date	Check #	Account ID	Line Description	Debit Amount	Credit Amount
		1308	Project Provost & Pritchard		3,472.16
9/26/25	33027	7009	office and shop cleaning, 3 weeks	420.00	
		1308	Sarah's Scottish Maids		420.00
9/26/25	33028	6005	Annual Farm Bureau Membership	265.00	
		1308	Farm Bureau		265.00
9/26/25	33029	5114	amount owed from 4 year audit	8,050.05	
		1308	Western Conf. Team. Pension		8,050.05
9/26/25	33031	7008 1308	shirts and sweatshirts Applejacks T-Shirts &	664.76	664.76
			Graphics		
9/26/25	33032	8005	after hours call from April, Lat #46	337.50	
		1308	J & J Pumps, INC		337.50
	Total		_	109,438.55	109,438.55



# STEVE MANNING CONSTRUCTION, INC.

GENERAL ENGINEERING CONTRACTOR CA LIC #754230

Attention ACID: September 5, 2025

BID DATE: September 5, 2025

**JOB DESCRIPTION:** ACID – Main Canal Priorities

**Steve Manning Construction, Inc.** is pleased to have the opportunity to quote to your firm the following items of work on the Spring Gulch, Panorama, and Trefoil/Jim Dandy Canal Shaping and Compacting Project.

### **Steve Manning Construction Inc (SMCI):**

1. Is a Union Contractor Signatory to the Operating Engineers Local 3 and Laborers Local 185 all prices include prevailing wage rates.

# SEE ATTACHED PAGE FOR BID ITEM PRICING AND SCOPE OF WORK (per attached ACID write up)

#### **SPECIAL CONDITIONS:**

- All underground to be located prior to work. SMCI will not be responsible for unmarked items.

#### **EXCLUSIONS:**

- 1. All SWPPP work (reports, inspections, implementation, installation, BMPs, etc.)
- 2. All permits and fees
- 3. All materials testing.
- 4. Surveying
- 5. Bonding
- 6. Liquidated Damages
- 7. Warranty
- 8. Driveway and street repair work.
- 9. Repair of Concrete Structures or Pipe Assemblies (unless negligently damaged by SMCI)

If you have any questions, or require additional information, please feel free to contact me.

Bill H Spoon
Bill Spoon

Project Manager

Thank you,

Steve Manning Construction Inc.

Cell: 530-605-5704 bspoon@smci-const.com

### **Priority #1**


# Panorama to Locust

### **Reach Location and Description:**

Approximately 11,000 feet of Anderson-Cottonwood Irrigation District's Main Canal between the Project Begin and End coordinates provided below:

Approximate Project Begin Coordinate: Lat: 40.241829, Long: -122.144135 Approximate Project End Coordinates: Lat: 40.235811 Long: -122.162594

- Stump and vegetation removal
- Reshape and Compact
- Potential soil import



# **Budget**

Description	Qty	Unit	Unit Cost	Total Cost
Panorama to	11,000	LF	\$73	\$803,000
Locust	11,000	<b>D</b> 1	Ψ	Ψουσ,σου

### **Priority #2**

# Crowley Gulch to Gas point Rd.

### **Reach Location and Description:**

Approximately 3400 feet of Anderson-Cottonwood Irrigation District's Main Canal between the Project Begin and End coordinates provided below:

Approximate Project Begin Coordinate: Lat: 40.224499, Long: -122.194091 Approximate Project End Coordinates: Lat: 40.225232, Long: -122.195735

- Stump and vegetation removal
- Reshape and Compact
- Potential soil import



# **Budget**

Description	Qty	Unit	Unit Cost	Total Cost
Crowley to Gas Point	3,400	LF	\$73	\$248,200

### **Priority #3**

# **Greengate to Ludwig**

### **Reach Location and Description:**

Approximately 2000 feet of Anderson-Cottonwood Irrigation District's Main Canal between the Project Begin and End coordinates provided below:

Approximate Project Begin Coordinate: Lat: 40.224499, Long: -122.194091 Approximate Project End Coordinates: Lat: 40.225232, Long: -122.195735 Remove vegetation, reshape/compact canal bank and access road



# **Budget**

Description	Qty	Unit	Unit Cost	Total Cost
Green Gate to Ludwig	2,000	LF	\$73	\$146,000

### **Description of the Work for Reshape and Compact**

**Mobilization/Demobilization, Insurance, and Permits:** Contractor shall provide all labor, materials, tools, equipment and incidentals necessary for mobilization, insurance, and licenses, required during the performance of the work as specified. This also includes demobilization, including the removal of all equipment, supplies, personnel and incidentals from the project at the end of construction.

**Miscellaneous Facilities and Operations:** Contractor shall make provisions for traffic control, worker and public safety protections, temporary access improvements such as gravel used for the Contractor's access during construction, protection of existing facilities, general project clean up, temporary power, and all costs for miscellaneous work not specifically mentioned in other work items below.

Vegetation Removal, Clearing and Grubbing: Contractor shall clear, grub, strip and dispose of vegetation from the canal levy down to the toe of the embankment and inside the water channel. This also includes the removal and disposal of trees, stumps, and root balls from canal embankment area. The Contractor shall reconstruct the embankment area where trees stumps were removed (refer to SPECIFICATIONS FOR CANAL EARTHWORK below). Generally, all vegetation shall be removed from the inside of the canal to the outer toe of the embankments. This item includes the hauling and off-site disposal of vegetation. Contractor may also burn removed vegetation if conditions permit.

**Fence Relocation:** Where fences exist, within the work area, on the top or outside slope of the Canal embankment, the Contractor shall remove the existing fence. Contractor will make every attempt to salvage existing fence materials. Unsuitable material will be gathered up and hauled off site to District property on Barney St. District Staff will coordinate relocation of removed fencing with landowners on an, as needed basis. If convenient for contractor to reinstall any incidental fence removal, District will supply fencing materials as requested. Fencing supplies will consist of T-posts, barbwire or hog panels.

Canal Shaping, Grading and Compacting: Contractor shall shape and grade the ACID Main Canal and levy within the limits of the Project including grading the canal bottom to drain downstream, trimming canal side slopes to achieve more uniform slopes.

Referencing to the minimum dimensions shown on the TYPICAL CANAL SECTIONS EXHIBIT. All inside and outside embankment slopes and embankment tops shall be compacted per the SPECIFICATIONS FOR CANAL EARTHWORK provided below. Canal embankments shall be built up to a minimum of 15-inches (±) of freeboard from the Canal historical high-water elevation. Historical high-water elevations are provided by the District

and painted on existing structures located along the canal reach included in the Project. The left bank canal access road shall be constructed to be a minimum of 12-feet (±) wide if not already so. Fill material on the embankment top and outside slopes shall be placed and compacted per the SPECIFICATIONS FOR CANAL EARTHWORK provided below. No fill material shall be placed on the inside slope except with prior authorization from the District. The Contractor shall also evenly distribute any excess material resulting from shaping and grading on the outside bank of the canal levy.

**Disposal or Disbursement of Unsuitable Materials:** Unsuitable materials that include only earthen material contaminated with organics that have already been cleared and grubbed may be spread evenly over the outside slope of the levy after construction is complete. Any unsuitable non-native materials found buried within the canal banks shall be disposed of.

Project Meetings and Construction Schedule: Once the "Green Light" is given to begin, the District will arrange and conduct progress meetings. These meetings shall be conducted weekly throughout the duration of the Project, unless scheduled otherwise and shall be attended by District staff, Contractor, and representatives of any subcontractors. The purpose of these meetings shall be to review the progress of the project and resolve any projected or unforeseen issues and verify projects progression.

#### SPECIFICATIONS FOR CANAL EARTHWORK

### 1. COMPACTION OF CANAL INSIDE SLOPES

Compaction of both canal inside slopes is required along the full extent of the canal included in the Project. Compaction shall be performed after grubbing, vegetation removal and canal shaping is complete resulting in a uniform trapezoidal channel free of vegetation and debris. Side slope compaction shall be performed by a universal compaction wheel, vibratory plate compactor or other compaction method with prior approval from the District. Compaction shall be performed with sufficient duration and number of passes to collapse rodent holes and voids made from removed vegetation and result in the existing embankment side slopes to be made firm and unyielding, to the satisfaction of the District.

Following inside canal slope compaction, the Contractor shall finish grade canal so the channel is smooth and free from loose earth material, debris, rocks, vegetation and indentations from compaction operations.

### 2. COMPACTION OF CANAL BOTTOM

Compaction of the canal bottom is required along the full extent of the canal included in the Project. Compaction shall be performed by a vibratory roller or other compaction method with prior approval from the District. Care should be taken to locate and prevent damage from compaction activities to existing underground structures and pipes. Compaction shall be performed with sufficient duration and number of passes to result in the existing canal bottom being made firm and unyielding and to the satisfaction of the District. Due to diverse soil structure throughout the district, firm and unyielding may not be achievable in certain areas. These areas should be brought to the Districts attention immediately to discuss options of a plan forward.

### 3. COMPACTION OF EMBANKMENT TOPS

Compaction of embankment tops is required along the full length of the canal included in the Project and includes both embankments where applicable. For portions of the canal where there is only one defined canal embankment (left embankment), only that embankment requires compaction.

Compaction shall be performed by a vibratory roller or other compaction method with prior approval from the District. Care should be taken to locate and prevent damage to existing underground structures and pipes from compaction activities. Compaction shall be performed with sufficient duration and number of passes to result in the existing embankment tops being made firm and unyielding and to the satisfaction of the District.

Following canal top compaction, the Contractor shall finish grade the embankment providing a smooth driving surface which slopes to drain away from the canal center.

### 4. COMPACTION OF OUTSIDE SLOPES OF EMBANKMENT

Compaction of canal outside slopes is required along the full length of the canal included in the Project and includes both embankments where applicable. For portions of the canal where there is only one defined embankment (typically left embankment), only that embankment side requires compaction.

Compaction shall be performed after grubbing and vegetation removal is complete. Side slope compaction shall be performed by a universal vibratory compaction wheel, vibratory plate compactor or other compaction method with prior approval from the District.

Compaction shall be performed with sufficient duration and number of passes to collapse

of rodent holes and voids made from removed vegetation and result in the existing embankment side slopes being made firm and unyielding, to the satisfaction of the District.

#### 5. PLACEMENT AND COMPACTION OF FILL MATERIAL

Placement and Compaction of fill material is anticipated in the following situations:

- Placement of fill material to raise embankment elevation to be 15-inches (minimum) above the high-water elevation in the canal.
- Placement of fill material to widen the canal drive access embankment (left bank) to 12-feet.
- Placement of fill material in voids in the canal embankment due to removal of vegetation, tree root balls, unsuitable material, or other objects.

Placement of fill materials shall be conducted per Section 5 – Specifications for Placement and Compaction of Fill Materials.

#### SPECIFICATIONS FOR PLACEMENT AND COMPACTION OF FILL MATERIALS

- a. Unless otherwise noted, placement and compaction of engineered fill materials for all fill areas shall be performed according to the provisions of the State Standard Specifications, Section 19-6.
- b. Embankment Material:
  - i. Contain a minimum fines content of 20;
  - ii. Have a Pl range between 10-25.
  - iii. Contain generally well-graded material with no rocks larger than 6inches, granted any cobbles are sufficiently mixed with smaller grained material such that no areas of nested cobbles exist.
  - iv. Organic material content shall not exceed 2% by volume.
- c. Subgrade Preparation: Before placing fill, scarify ground surface to a depth of 8 inches below the original ground surface to provide ample bond between old and new material. Compact scarified ground surface to 95% relative

- density (ASTM D1557). Do not backfill over porous, wet, or spongy subgrade surfaces.
- d. Compaction of Fill Materials: All fill shall be compacted to a minimum of 95% relative density (ASTM D1557). Place fill material in layers not exceeding 8 inches, loose measurement. Compact each layer before placing the next layer. As the compaction of each layer progresses, continually level and manipulate to ensure uniform moisture content and density. Add water to obtain optimum moisture content. Removal of excess water shall be accomplished through aeration by plowing, blading, disking, or other methods satisfactory to the Engineer. The excavation, placing, moistening, and compacting operations shall be such that the material will be uniformly compacted and will be homogeneous, free from lenses, pockets, streaks, voids, and laminations or other imperfections such that the materials when compacted will be blended sufficiently to achieve the required density.
- e. Keyed Benching into Existing Slopes and embankment excavations
  - As shown and described on the TYPICAL CANAL SECTIONS EXHIBIT (attached), new embankment fill material shall be keyed into the existing slope.
  - ii. Where traditional tracked equipment can be used for spreading fill materials, this can be executed with the use of a dozer blade, excavator or similar equipment.
  - iii. Benching into the existing slope can occur during the spreading and compacting phase of work.
  - iv. In sliver fill areas, the benching shall be performed prior to the placement of fill.
  - v. After benching of existing slope, the Owner's Representative shall inspect embankment for suitability of existing soils.
- f. Embankments shall be constructed to top widths and side slopes as shown on the TYPICAL CANAL SECTIONS EXHIBIT (attached). Materials for embankments shall be obtained from the District stockpile or from another source with prior authorization from the District. All borrow material must comply with this specification.

- g. If unsuitable material is found to be present in the existing embankment, additional excavation and material blending or import may be required as directed by the District.
- h. Moisture Conditioning: Fill material shall be moisture conditioned in order to meet compaction requirements with optimum moisture content (±2%).
- i. Non-native, sandy, and cohesionless materials found within the canal embankment, shall be removed as outlined below.
  - i. Non-native, sandy, and cohesionless material found within the canal embankments shall be removed vertically and/or horizontally no less than 12 inches beyond the unsuitable layer, or 2 feet below the canal invert, whichever is less, or as directed by the District. Replaced fill shall meet Embankment Material specifications as identified is part 5b of this Section.
  - ii. Sandy and cohesionless materials shall be blended with other earthen clayey materials unless directed otherwise by the District.
  - iii. Non-native materials (i.e. concrete rubble) shall be disposed of as unsuitable material as directed by the District.

### 7. PROJECT SITE TESTING

- a. All placement of fill material in or against the canal embankments shall be subject to compaction testing by the Owner.
- b. All sampling, specimen preparation, and testing of materials shall be in accordance with the standards of nationally recognized technical organizations.
- c. Contractor shall give District timely notice (48 hours minimum) of readiness of the Work for all required inspections, tests, or approvals and shall cooperate with inspection and testing personnel to facilitate required inspections or tests.
- d. Except for specified material suitability tests, all initial routine tests of materials shall be at the expense of the District and shall be performed by an independent certified laboratory designated by the District. Whenever a specified percent relative compaction test is required and the material or portion thereof so tested fails to meet or exceed the relative compaction

- specified, all subsequent retesting shall be performed at the expense of the Contractor.
- e. Upon receipt of notice, Contractor shall correct all defective or rejected Work and replace it with Work that is not defective, at no cost to the District.
- f. When employed, typical compaction testing frequency for canal embankments: At least 1 test per lift per 1,000 sf of surface area or every 200 lineal foot of embankment, or 2,000 cubic yards of fill placed, whichever is more frequent.

# **Water Efficiency Project**

**Churn Creek Bottom** 

### **Churn Creek Bottom**

The overall theme for the 2025/2026 off season is to fix leaking pipes, raise the banks, reshape and compact as many ditches as possible. The objective of the proposed work is to improve overall water efficiency, capacity, and access for Staff to do maintenance and repairs to the entire system. Every proposed reach will have consistent challenges. These challenges drive the overall scope of work. The basic scope of work is to increase capacity by reshaping, compacting, raising the canal banks 6" or more, and repair leaking pipes system wide.

Contractor will remove/grub vegetation from the ditch bank, reshape and compact each section of open ditch. Erosion control measures are to be taken on the upstream and downstream sides of any road or driveway crossing and check structures. All erosion control will be installed by the contractor. Any existing erosion control will be removed and replaced after reshaping if agreed to be suitable and practical to leave through coordination of the Contractor and District. District will use temporary labor and/or district staff to reinstall fencing when necessary. Reaches are shown below. The District will purchase and store materials for project use:

- Erosion control materials
  - -Engineer Stone 6-12" \$36/ton
  - -3"x8" Crush-\$23.50/ton
- Fencing supplies and tools
  - -6' T-posts \$6.50 ea. w/ clips
  - -1320 ft roll of barbed wire \$83 per roll
  - -16'x50" fence Panels \$40 each
- **Suitable fill**-soil (clay)to be trucked from source
  - -Market price from source

#### **Obstacles/Challenges:**

- -Fences on or too close to the ditch bank needing to be relocated and should be identified before work begins.
- -Driveway and Road crossings that require custom earth work and erosion control measures
- -Headwalls and checks that will also require custom earth work and erosion control measures
- -One side of ditch is too small to access. Difficult access overall.

- -Vegetation-Working around large oak trees close to or on the ditch bank that should be considered for saving
- -Not enough soil to salvage for a consistent shape water channel

#### **Description of the Work for Reshape and Compact**

**Mobilization/Demobilization, Insurance, and Permits:** Contractor shall provide all labor, materials, tools, equipment and incidentals necessary for mobilization, insurance, and licenses, required during the performance of the work as specified. This also includes demobilization, including the removal of all equipment, supplies, personnel and incidentals from the project at the end of construction.

**Miscellaneous Facilities and Operations:** Contractor shall make provisions for traffic control, worker and public safety protections, temporary access improvements such as gravel used for the Contractor's access during construction, protection of existing facilities, general project clean up, temporary power, and all costs for miscellaneous work not specifically mentioned in other work items below.

Vegetation Removal, Clearing and Grubbing: Contractor shall clear, grub, strip and dispose of vegetation from the canal levy down to the toe of the embankment and inside the water channel. This also includes the removal and disposal of trees, stumps, and root balls from canal embankment area. The Contractor shall reconstruct the embankment area where trees stumps were removed (refer to SPECIFICATIONS FOR CANAL EARTHWORK below). Generally, all vegetation shall be removed from the inside of the canal to the outer toe of the embankments. This item includes the hauling and off-site disposal of vegetation. Contractor may also burn removed vegetation if conditions permit.

**Fence Relocation:** Where fences exist, within the work area, on the top or outside slope of the Canal embankment, the Contractor shall remove the existing fence. The Contractor will make every attempt to salvage existing fence materials. Unsuitable material will be gathered up and hauled off site to District property on Barney St. District Staff will coordinate relocation of removed fencing with landowners on an, as needed basis. If convenient for contractor to reinstall any incidental fence removal, District will supply fencing materials as requested. Fencing supplies will consist of T-posts, barbwire or hog panels.

Canal Shaping, Grading and Compacting: Contractor shall shape and grade the ACID Main Canal and levy within the limits of the Project including grading the canal bottom to drain downstream, trimming canal side slopes to achieve more uniform slopes.

Referencing to the general dimensions shown on the TYPICAL CANAL SECTIONS EXHIBIT.

All inside and outside embankment slopes and embankment tops shall be compacted per

the SPECIFICATIONS FOR CANAL EARTHWORK provided below. Canal embankments shall be built up to 8"(+/-) freeboard from the Canal historical high-water elevation or match grade at existing check structures. Historical high-water elevations are provided by the District and painted on existing structures located along the canal reach included in the Project. The left bank canal access road shall be constructed to be a minimum of 8 feet (±) wide if not already so. Fill material on the embankment top and outside slopes shall be placed and compacted per the SPECIFICATIONS FOR CANAL EARTHWORK provided below. No fill material shall be placed on the inside slope except with prior authorization from the District. The Contractor shall also evenly distribute any excess material resulting from shaping and grading on the outside bank of the canal levy.

**Disposal or Disbursement of Unsuitable Materials:** Unsuitable materials that include only earthen material contaminated with organics that have already been cleared and grubbed may be spread evenly over the outside slope of the levy after construction is complete. Any unsuitable non-native materials found buried within the canal banks shall be disposed of or used for erosion control.

Project Meetings and Construction Schedule: Once the "Green Light" is given to begin, the District will arrange and conduct progress meetings. These meetings shall be conducted weekly throughout the duration of the Project, unless scheduled otherwise and shall be attended by District staff, Contractor, and representatives of any subcontractors. The purpose of these meetings shall be to review the progress of the project and resolve any projected or unforeseen issues and follow progression.

#### SPECIFICATIONS FOR CANAL EARTHWORK

#### 1. COMPACTION OF CANAL INSIDE SLOPES

Compaction of both canal inside slopes is required along the full extent of the canal included in the Project. Compaction shall be performed after grubbing, vegetation removal and canal shaping is complete resulting in a uniform trapezoidal channel free of vegetation and debris. Side slope compaction shall be performed by a universal compaction wheel, vibratory plate compactor or other compaction method with prior approval from the District. Compaction shall be performed with sufficient duration and number of passes to collapse rodent holes and voids made from removed vegetation and result in the existing embankment side slopes to be made firm and unyielding, to the satisfaction of the District.

Following inside canal slope compaction, the Contractor shall finish grade canal, so the channel is smooth and free from loose earth material, debris, rocks, vegetation and indentations from compaction operations.

#### 2. COMPACTION OF CANAL BOTTOM

Compaction of the canal bottom is required along the full extent of the canal included in the Project. Compaction shall be performed by a vibratory roller or other compaction method with prior approval from the District. Care should be taken to locate and prevent damage from compaction activities to existing underground structures and pipes. Compaction shall be performed with sufficient duration and number of passes to result in the existing canal bottom being made firm and unyielding and to the satisfaction of the District. Due to diverse soil structure throughout the district, firm and unyielding may not be achievable in certain areas. These areas should be brought to the Districts attention immediately to discuss options of a plan forward.

#### 3. COMPACTION OF EMBANKMENT TOPS

Compaction of embankment tops is required along the full length of the canal included in the Project and includes both embankments where applicable. For portions of the canal where there is only one defined canal embankment (left embankment), only that embankment requires compaction.

Compaction shall be performed by a vibratory roller or other compaction method with prior approval from the District. Care should be taken to locate and prevent damage to existing underground structures and pipes from compaction activities. Compaction shall be performed with sufficient duration and number of passes to result in the existing embankment tops being made firm and unyielding and to the satisfaction of the District.

Following canal top compaction, the Contractor shall finish grade the embankment providing a smooth surface which slopes to drain away from the canal center.

#### 4. COMPACTION OF OUTSIDE SLOPES OF EMBANKMENT

Compaction of canal outside slopes is required along the full length of the canal included in the Project and includes both embankments where applicable. For portions of the canal where there is only one defined embankment (typically left embankment), only that embankment side requires compaction.

Compaction shall be performed after grubbing and vegetation removal is complete. Side slope compaction shall be performed by a universal vibratory compaction wheel, vibratory plate compactor or other compaction method with prior approval from the District.

Compaction shall be performed with sufficient duration and number of passes to collapse rodent holes and voids made from removed vegetation and result in the existing embankment side slopes being made firm and unyielding, to the satisfaction of the District.

#### 5. PLACEMENT AND COMPACTION OF FILL MATERIAL

Placement and Compaction of fill material is anticipated in the following situations:

- To raise embankment elevation to be 8 inches(+/-) above the high-water elevation in the canal.
- To widen the canal access embankment to 8-feet.
- In voids in the canal embankment due to removal of vegetation, tree root balls, unsuitable material, or other objects.
- Where there is not enough salvageable material to achieve a uniform trapezoidal channel

## **Main Canal**

#### PRIORITY #2-MC I-5 Rentals to Smith Rd 5000ft

This section is riddled with rodent holes in the top 18" and lows spots that reduce capacity. There are also multiple large oak trees on this reach along with vegetation that needs to be removed. When canal levels are raised to irrigation height water leaks out of the canal on the residential side and saturates the adjacent properties. Adjacent 2500ft of fencing on the residential side will impede access and need to be relocated after construction.




Description	Qty	Unit	Unit Cost	Total Cost
I-5 Rentals to Smith Rd	5000	LF	\$55-\$65	

## **Main Canal**

### PRIORITY #1- MC Smith to Knighton-9500ft-reshape-compact

This section needs to be grubbed of vegetation, reshaped, and banks raised 8" or more to increase overall capacity. Over time the bank has settled or eroded away, been damaged by cattle and has approximately 2000 feet of fencing to be relocated



Description	Qty	Unit	Unit Cost	Total Cost
Smith Rd. to	9500	LF	\$55-\$65	
Knighton				

## **Freeway Ditch**

## **Priority #1 TA to Duncan** – 3000ft


Open Ditch portion starts behind the TA truck stop on Pacheco Rd. and continues through Duncan Ln.



Description	Qty	Unit	<b>Unit Cost</b>	<b>Total Cost</b>
TA to Duncan	3000	LF	\$55-65	

## Freeway Ditch

## PRIORITY #2 -Peach Lane - 760ft



Description	Qty	Unit	<b>Unit Cost</b>	<b>Total Cost</b>
Peach Lane	760	LF	\$55-\$65	

## **Leaking Pipes – Churn Creek**

The general scope of work is to remove and replace existing pipelines, connecting the new pipe to existing infrastructure. The District will purchase all materials needed for the project. Contractor shall excavate, remove and dispose of existing pipelines.

### MC Golf course-200ft leaking pipe 48"

200ft – 48" HDPE @ 87.13/ft = \$17,426 plus Tax and delivery

8 – 48" Mar Mac Poly seal coupler - \$250 each = \$2064 plus tax and delivery

Estimated-\$30,000 in contracted services

Pipe leaks into the golf course maintenance yard when water is in the pipe. Past repairs have connected dissimilar pipes. The connecting pipe is undersized, leaks at the connection and is a point of restriction. Replace entire 200 feet of pipe from headwall with 48' HDPE to increase water efficiency



### **Churn Creek Bottom**

### MC Countryside lane- 150ft leaking pipe 36" concrete pipe

This section of 36" concrete pipe has progressively gotten worse over the 2024-2025 water season and needs to be replaced from box to box. It now leaks for a period of 4 days while water is in the pipe and floods across Countryside Lane and down a driveway. At peak levels the water loss is equivalent to a 6"- 8" pipe

180 ft - 36" HDPE @ \$57/ft = \$10,260 plus tax and delivery

7 - Mar Mac 36" Poly seal coupler - \$201 each = \$1407 plus tax and delivery

Estimated - \$30,000 contracted services to install



## A.C.I.D. Pipe Replacement

## **Lateral 29 Pipe Replacement- 700'section(approx.)**

Lateral 29 conveys water to multiple customers. The section of pipe spans approximately 700 feet. This section, 24" re-enforced concrete pipe with head walls, has reached the end of Its life cycle. Water has eroded around the head walls, shifted them, and caused separation from the pipe. The pipe leaks an unknown amount of water during the irrigation season which could otherwise be utilized for beneficial use.



Description	Qty	Unit	Unit Cost	Total Cost
Lateral 29	700	LF		

## Lateral 29.2 Pipe Replacement- 1600' section(approx.) – 24" PVC

Lateral 29.2 conveys water to multiple customers. This 30" corrugated metal section of pipe is both underground and above ground. The above ground portion of this section is supported by concrete saddles. Both the above ground portion and the supporting saddles have reached the end of their life cycle. The section of pipe spans 1600 feet and crosses four different parcels.

The saddles have separated from the pipe in specific sections giving no support to the pipe itself. The water has corroded the pipe to such an extent that the integrity of the pipe and unions are compromised. The pipe leaks an unknown amount of water during the irrigation season which could otherwise be utilized for beneficial use.



Description	Qty	Unit	Unit Cost	Total Cost
Lat 29 Hereford	1700	LF		

### Lateral 33 Broken Pipe- 1250ft 24"

This section of pipe has also reached the end of its' life cycle and needs total replacement. The section has a headwall at the entrance and exit that will need to be replaced. There is a distribution structure that will also need to be considered for replacement or reconnecting to.



Description	Qty	Unit	Unit Cost	Total Cost
Lat 33 Lonetree	1250	LF		

## **Scope of Work**

A.C.I.D will supply 24" 80 PIP PVC pipe for job, any connection fittings and job specific pre casted distribution boxes. Supplies to be ordered and on hand before start of work. Contractor will perform entire job.

- Clear any vegetation impeding access to project
- Remove and replace fences for access
- Remove existing infrastructure and haul off
- Establish grade
- Place 4-6" of rock bedding for pipe to lay on

- Install head walls build in place or use precast material
- Pour-in-place pipe saddles
- Install distribution boxes
- Install pipe
- Complete connections
- Back fill with existing and/or imported soil
- Apply Protective coating to exposed pipe.
- Leave job site clean when complete

Mobilization/Demobilization, Insurance, and Permits: Contractor shall provide all labor, materials, tools, equipment and incidentals necessary for mobilization, insurance, and licenses, required during the performance of the work as specified. This also includes demobilization, including the removal of all equipment, supplies, personnel and incidentals from the project at the end of construction.

**Miscellaneous Facilities and Operations:** Contractor shall make provisions for worker and public safety protections, temporary access improvements such as gravel used for the Contractor's access during construction, protection of existing facilities, general project clean up, temporary power, and all costs for miscellaneous work not specifically mentioned in other work items below.

**Vegetation Removal, Clearing and Grubbing:** Contractor shall clear, grub, strip and dispose of vegetation 5'-10' on both sides of new pipeline or from the work area. This also includes the removal and disposal of trees, stumps, and root balls. Generally, all vegetation shall be removed from the work site. This item includes the hauling of removed vegetation to an off-site disposal location. Contractor may also burn removed vegetation if conditions permit.

**Fence Relocation:** Where fences exist, within the work area the Contractor shall remove the existing fence. The Contractor will make every attempt to salvage existing fence materials to put back after work is complete. If removed fencing is unsuitable for replacement, the District will supply fencing materials as requested. Fencing supplies will consist of T-posts, barbwire or hog panels.

## 2025/2026 Off-Season Work - Staff

#### **New Grilles**

- 1. Hill Ditch Pipe
- 2. Lateral 29 @ MC
- 3. Lat 29 Hereford
- 4. Broadhurst
- 5. Lat 27 on MC
- 6. Lat 21.3 Orchard valve
- 7. Lat 29 Grimsman
- 8. Lat 3 Pioneer Grille

### **Diversion Facility**

- Replace I-Beams on fish screen (contractor?)
- 2. Lubricate and maintenance trash rake
- 3. Inspect and repair Drum Gate
- 4. Clean/polish fish viewing windows

### Main Canal - De-veg/Compact

- 1. Broadhurst de-veg, roller compact behind gingerbread house
- 2. MC-Low spot between school ditch and Stayley- clear veg grade road

### Area 1 (Redding)

- 1. De veg Main canal from HWY 44 to Clear Creek siphon CAL FIRE
- 2. Leak at Juniper School
- 3. Board Slot/Grille Pioneer
- 4. Clean Lateral 3 Pioneer to Mulberry
- 5. Live oak siphon- inspect grille, clear debris in, on, and around siphon

### Area 3 (Churn Creek)

- 1. Smith Road Split remove and re-level blocks
- 2. Clean out lined section with Skid steer
- 3. Improve turn out Niles Lane (Launa)
- 4. 9'x15" countryside lane valve-replace
- 5. Danish way valve-gravel pant inspect/replace
- 6. Holstein check-dirt work
- 7. Mortar Green Meadows Box (Pablo)
- 8. Gopher holes 19919 Country side lane (Kristen)-530-355-7870

## 2025/2026 Off-Season Work - Staff

- 9. School Ditch Ivar's valves
- 10. Repair leaking turn outs behind TA
- 11. Remove wood from banks- end of Weeks Rd

#### Area 21

- 1. Lateral 21 siphon Deschutes Xing
- 2. Lateral 21 siphon- Shady Ln. to S-Turn(inspect for leaks)
- 3. Lateral 21 Bill Robinsons pipe(s-turn pond)
- 4. Lat 21.3 clear and repair Cindy Lakes box
- 5. Lateral 19 Missouri drain into lateral
- 6. Lat 27 pallet ditch- veg reshape
- 7. Lat 27 veg reshape eucalyptus grove Hawes/Hopson
- 8. Shady Lane Pipe line
- 9. Slide gate twin oaks
- 10. Rip rap new turn out at Spring Gulch

#### Area 5

- 1. Patricia Harman-Pick up Ditch- install 900 ft of 24" pipe
- 2. Josh Daveys ditch to Leedy
- 3. Leedy cut and treat
- 4. Pick up ditch pond dump valve
- 5. Target practice box- mortar inside and seal leaks
- 6. Lat 35-Joanna Brown-leaking pipe
- 7. Lat 35 Cliff's Check
- 8. Little web slide gate Johna
- 9. 4555 webb Rd- leaking pipe between boxes-Arbiso-Johna
- 10. Lat 35- replace slide gates in box that irrigates Tonja-Johna

#### Area 6

- 1. Frank Bernard ditch Lateral 51
- 2. Raise sides 6" on Bobbin Flume???
- 3. Floyd Lane to Adams
- 4. I-5 to Bengard
- 5. Sheree Koufield valve(Smith Bottom)
- 6. Lat 41- pipe leaks under road @ alfalfa lid